# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16937

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/11/2014-15, Date: 25.03.2015**

**Road Development and concrate road works at Kuvempunagar 2nd Stage Main road in ward no. 11.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of N KEERTHI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 177 | Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 105.58 | Rupees One Hundred Five and Fifty Eight Paise Only |
| 2 | 177 | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4834.92 | Rupees Four Thousand Eight Hundred Thirty Four and Ninety Two Paise Only |
| 3 | 115 | Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification etc complete as per specifications and directions of engineer in charge of the work | M | 137.89 | Rupees One Hundred Thirty Seven and Eighty Nine Paise Only |
| 4 | 147.5 | Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 5837.89 | Rupees Five Thousand Eight Hundred Thirty Seven and Eighty Nine Paise Only |
| 5 | 1180 | Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work | Sqm | 96.96 | Rupees Ninety Six and Ninety Six Paise Only |

| | | | | | |
|---|---|---|---|---|---|
| 6 | 2.97 | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work | Cum | 6050.12 | Rupees Six Thousand Fifty and Twelve Paise Only |
| 7 | 1.78 | Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work | Qtl | 7955.86 | Rupees Seven Thousand Nine Hundred Fifty Five and Eighty Six Paise Only |
| 8 | 165.18 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Sqm | 383.52 | Rupees Three Hundred Eighty Three and Fifty Two Paise Only |
| 9 | 177 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 72.53 | Rupees Seventy Two and Fifty Three Paise Only |

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**